Prepared by:

Kyle Andrzejewski
Kyle@Westside-Solutions.com
(989) 464-8346

WESTSIDE SOLUTIONS

Date:
10/28/2026

Prepared for:

Village of Northport
105 S Bay Street
Northport, MI 49670
Attn: Jered Ottenwess

Sourcewell Contract #021825-CPI

Item	Model	Description	Qty	Price	Total
Charging Station Model	EXPS-T104P1DS-200F2-10A6L5-CR-ETN	Express Solo DC, NA, 200kW, 480VAC, dual simultaneous ports, 2 expansion outputs to Power Link, 1 ACMs, 2 DCMs, fine switching, 600kW max cabinet, 381mm touch display, CC & RFID, cell/WiFi/ethernet, 2x CCS1 400A 5.2m cut resistant, OmniPort	1	$74,340.00	**$74,340.00**
Concrete Mounting Template	EXP-ST1K-DPB2K-CMT-ETN	Metal bracket for proper alignment of conduits and bolt locations for positioning Express Solo T1000 and Power Block 2000 with cable entrance from below. Metric Units. ChargePoint label.	1	$345.00	**$345.00**
Misc	EXP-ST1K-DPB2K-CABLE-JIG-ETN	Cable jig for proper alignment of conductors for positioning Express Solo T1000 and Power Block 2000 from below. ChargePoint label.	1	$815.00	**$815.00**
Professional Cloud Plan	CP-SW-STE-PROFESSIONAL-DC-1P-60M	60 month Professional Cloud Plan for DC, 1 Port. Includes: all Core plan features, Public Sharing, Pricing Control, Tap to Pay, Custom screen, session limits. Subject to hardware compatible. New station req. Activation & 12-mo. min purchase	2	$3,206.25	**$6,412.50**
Assure Warranty	CP-ASSURE-SOLO-200-1S-60M	ChargePoint Assure for Express Solo 200 kW stations. Includes parts and labor coverage, network operating center (NOC) monitoring, targeted services levels and performance reporting. Priced per station. 60 Months.	1	$12,611.25	**$12,611.25**
Commissioning	CP-COMMISSIONING-SOLO	Required with purchase of Express Solo. Includes on-site validation of the make ready and installation, software updates, and hardware configuration. Any critical non-conformities identified must be resolved to activate DC hardware. Priced per station.	1	$1,750.00	**$1,750.00**
Activation	CP-ACTIVATION	Initial Station Activation & Configuration Service includes activation of cloud services and configuration of radio groups, custom groups, connections, access control, visibility control, pricing, reports and alerts. One time initial service per station.	1	$249.00	**$249.00**
Shipping	Freight to Contractor or Site		1	$2,500.00	**$2,500.00**
Skins	Branded customer skins for Charging Stations		1	$600.00	**$600.00**
Estimated Installation	**Includes:** Provide and install (1) H-frame pedestal for new service disconnect switch. Provide and install (1) 400-amp Nema 3R SER fusible disconnect switch with 350A fuses on H-frame. Provide and install (1) 350-amp feed from disconnect to (1) Express Solo 200 charging station. Provide and install (4) bollards. (2) bollards in front of charging station and (2) in front of service pedestal for vehicle protection. Provide and install (1) concrete foundation for Express Solo 200 charging station. Provide labor to install (1) Express Solo 200 charging station. Includes allowance of $1,800 for painting new parking stalls. Includes allowance of $3,000 for creation of engineering drawings if required. Includes electrical permit and inspections. **Notes:** Proposal is based upon the green space between the road and the parking lot provides adequate space for electrical/charging equipment, does not require a setback variance, and is not inside the ROW. Proposal does not include any utility cost. Commodity price changes exceeding 2% may require project cost adjustment. Arc flash study and coordination are excluded. Shunt trip wiring or breakers are excluded unless noted otherwise. Payment and performance bonds are excluded. Prevailing wages or other labor requirements are excluded unless noted otherwise. Site conditions to be verified prior to approval. Adequate working space to be provided on site by customer. Does not include finished landscaping. Site to be restored to rake finish and seeded. Does not include concrete/asphalt cutting and or patching unless otherwise noted. Does not include primary wiring or conduit, transformer, concrete pad, or metering. Metering assumed to be from CTs mounted in utility transformer. Does not include survey costs unless otherwise noted. Does not include future conduits or underground junction boxes unless otherwise noted. Does not include modification/adding to stormwater drainage system. Existing parking lines are to be covered by sealcoat and new lines painted. Grinding of existing lines not included. Does not include costs due to unforeseen soil conditions, including but not limited to soil contamination, rock, or unmarked obstructions. Local disconnects for charging stations are not included as equipment is in the line of site from main electrical panel. Proposal does not include modifying the grade of parking area, sidewalks, or ramps for ADA compliance if necessary. Proposal does not include any additions or modifications to existing parking lots unless otherwise noted. Buy America compliant materials are not included unless otherwise noted. Proposal does not include the removal of any trees, stumps, or roots and assumes they will be removed prior to installation unless otherwise noted. Proposal does not include costs associated with dewatering site if necessary.				**$95,000.00**
New Power/Primary Install (Utility)	Utility side infrastructure and installation costs to be provided by utility provider				**TBD**
Westside Solutions Inc Project Sub Total					**$194,622.75**

Quote valid for 30 days - Quote does not include applicable sales tax