



ELECTRICAL SERVICES WITH A CHERRY ON TOP!

1039 Schmidt Way Traverse City, MI 49696

231-590-8516

cherrycapitalelectric@gmail.com

Project Proposal

Proposal Submitted to: Village of Northport ATTN: **Joni Scott**

Date: **3/18/26**

Provide all labor, equipment and materials to perform the following work:

Install/Replace Qty.(2) Damaged Light Poles

Price Includes:

- Removal and disposal of of any existing pole/pole base & damaged wiring, if any.
- Wiring & assembly of new light poles with supplied accessories.
- Light poles supplied are to be as described below.
- Preperation of existing pole bases to acomodate new light poles.
- Installation of light poles and testing of proper function.

Project Total: \$17,600.00

Acceptance of Proposal

The above prices, specifications and conditions are satisfactory

And are hereby accepted.

You are authorized to do the work as specified.

Signature: _____

Date: _____

Name: Christopher Hayes

Phone #: _____
231-590-8516

Email: cherrycapitalelectric@gmail.com

Note: This proposal may be withdrawn by us if not accepted within
15 days.

"Pay when Paid" contract clauses will not be considered by
Cherry Capital Electric LLC.

Payment to be made as follows:

Net 10. 50% due upon proposal acceptance. Remaing balance due upon project completion. Any invoices outstanding after 30 days are over due and are subject to a service charge of 1 ½% per month. Should it be necessary to place a past due invoice(s) with an attorney or collection agency, Buyer agrees to pay all reasonable collection costs and attorney fees in addition to all other sums due. Disclaimer of All Warranties: THERE ARE NO OTHER WARRANTIES EITHER EXPRESS OR IMPLIED PROVIDED. ALL WARRANTIES, EXPRESS OR IMPLIED, INCLUDED IMPLIED WARRANTIES OF FITNESS ARE EXPRESSLY EXCLUDED.

1039 SCHMIDT WAY TRAVERSE CITY, MI 49696

Type	Qty	Catalog
BREAK AWAY	#	
	2	ESPL2P2030KASSB6SS-AO BHDF13 BHC48/1 NYA14F5J17P08BK-PROVS BWKT TRANSP FGIUS (2) BA24 PBA24 AB RFD248019

*** NOTES:

- CHANGED POLE SHAFT TO "F5J" IN ORDER FOR IT TO PASS WINDLOADING.
- ADDED "AO" OPTION, BREAK-AWAY KIT, TRANSPOS, BANNER ARMS AND PLANTER ARM

Esplanade LED Pedestrian Series, ESPL2, LED Performance Package 20, 3K, Auto-Sensing (120-277V), Quick Lock Stem Mount, Black, Shallow Symmetric, Shallow Skirt For Cutoff Requirement *263TXG

BOSTON HARBOR LEVELING FITTER FOR QUICK STEM MOUNT.
BLACK

BOSTON HARBOR SINGLE ROADWAY ARM, 48" LONG. BLACK
*263RNE

NORTH YORKSHIRE ALUMINUM POLE, 14' TALL, 3"X5" TENON, PROVISIONS, 17" BASE.
BLACK
* 263RNH

BEARING PLATE AND SKIRT. HOT DIPPED GALVANIZED BEFORE BLACK FINISH

SET OF 3/4" TRANSPO COUPLINGS.

GFI RECEPTACLE WITH SMALL IN-USE COVER. BLACK

BOLT-ON BANNER ARM, 24" LONG, 1" DIAMETER PIPE WITH BALL FINIAL. BLACK

BOLT-ON PLANTER BANNER ARM, 24" LONG, 1" DIAMETER PIPE WITH BALL FINIAL, EYEBOLT. BLACK

*263TG7 3/4"X18" ANCHOR BOLTS INCLUDED

LEAD TIMES AT 12 WEEKS DUE TO TRANSPO BREAK AWAY COUPLINGS REQUIRED BY MDOT

QUOTE VALID UNTIL
3/31/26

TO MATCH 2017
ASSEMBLY

10 TO 12 WEEK LEAD
TIME